



- NOTES
1. 4000PSI CONCRETE AT 28 DAYS
 2. REINFORCEMENT STEEL PER ASTM - A-185,A-615
 3. 1/2" CHAMFER AROUND TOP
 4. WHERE THE CONDITIONS OF USE AND CONSTRUCTION ARE BEYOND THE CONTROL OF THE MANUFACTURER OR SELLER, DTP ASSUMES NO RESPONSIBILITY FOR THE RESULTS OBTAINED FROM THE USE OF THIS PRODUCT.
 5. DRAWING NOT TO SCALE
 6. CONTRACTOR TO SUPPLY ALL CONDUIT, ANCHOR BOLT SETS, AND COUPLINGS.

AUGUST 2006

NOTE: OTHER SIZES AVAILABLE ON REQUEST

SHEET
1 OF
1

PRECAST
30" DIAMETER LIGHT POLE BASE
WITH EXTENDED BASE

GARDEN STATE PRECAST
FARMINGDALE, N.J.
PHONE #: 732-938-4436 FAX #: 732-938-6069

ELT-8