



- NOTES:**
- 4,000 PSI CONCRETE AT 28 DAYS.
 - REINFORCEMENT BARS PER ASTM A-615, GRADE 60 WELDED WIRE FABRIC PER ASTM A-185, GRADE 70
 - DESIGN LOADING AASHTO HS25-44.
 - CONSTRUCTION JOINT SEALED W/ 1" BUTYL MASTIC STRIP.
 - ANY ALTERATION TO THIS DRAWING MUST BE SUBMITTED TO GSP IN WRITING PRIOR TO PRODUCTION.
 - WATER TABLE DESIGNED AT 3' BELOW SURFACE (STRUCTURE IS NOT TO BE INSTALLED 5' BELOW GRADE)
 - FRAMES AND COVERS ARE DESIGNED FOR TRAFFIC AREAS
 - STRUCTURAL DESIGN IN ACCORDANCE WITH ASTM C-857-07 AND ACI-318.
 - MANUFACTURED IN ACCORDANCE WITH ASTM C-858-09.

HEAVIEST PICK:
 84" BASE = 12,000 LBS.
 8" TOP = 23,400 LBS.

LIFTERS:
 (4) 6" UTILITY ANCHORS IN FLOOR
 (4) 6" UTILITY ANCHORS IN TOP SLAB

- MATERIAL LIST**
- (1) 12" x 12" x 4-1/2" SUMP
 - (32) 1/2" PLASTIC INSERTS
 - (4) 1" X 14.5' CONSEAL 102 MASTIC
 - (8) 6" UTILITY ANCHORS FOR LIFTING

SCALE 3/4" = 1'

REV	BY	CK'D	DATE
DRAWN BY RR 6/11/2009			

4' x 6' x 7' FULLBOX
 WITH 38 1/2" OPENING
 FOR TRAFFIC AREAS



GARDEN STATE PRECAST
 P.O. BOX 702
 FARMINGDALE, NJ 07727
 732-938-4436
 732-938-6069 - FAX