



ELEVATION

NOTES

- 1. 4000 PSI CONCRETE AT 28 DAYS.
- 2. RISERS, CONES AND SLABS IN ACCORDANCE WITH ASTM C-478, LATEST REVISION.
- 3. INVERT LOCATION TO WITHIN A TOLERANCE OF +/- 1INCH.
- 4. ANY DEVIATION FROM THIS DRAWING MUST BE MADE TO GSP IN WRITING PRIOR TO PRODUCTION.
- 5. STEEL REINFORCED COPOLYMER STEPS AT 12" O.C. STARTING 30" OFF FLOOR.

SEPTEMBER 2019

T OF 1

SIZES AVAILABLE 48" / 60" /72" /84" /96" DIAMETER

FLEXIBLE PIPE SEAL AS REQUIRED

STEEL REINFORCED COPOLYMER STEPS

12" O.C.

AS REQUIRED .

PLAN VIEW

CAST IN DOOR AS REQUIRED

TOP SLAB PLAN VIEW

PRECAST WET WELL WITH TOP SLAB

GARDEN STATE PRECAST FARMINGDALE, N.J. PHONE #: 732-938-4436 FAX #: 732-938-7096

SAN-