



- NOTES:
1. 4000 PSI CONCRETE AT 28 DAYS.
 2. RISERS, CONES AND SLABS IN ACCORDANCE WITH ASTM C-478, LATEST REVISION.
 3. INVERT LOCATION TO WITHIN A TOLERANCE OF +/- 1 INCH.
 4. ANY DEVIATION FROM THIS DRAWING MUST BE MADE TO GSP IN WRITING PRIOR TO PRODUCTION.
 5. STEEL REINFORCED COPOLYMER STEPS AT 12" O.C. STARTING 18" OFF FLOOR.

SAN-1A

SEPTEMBER 2019

<p>SHEET 1 OF 1</p>	<p>WEIGHT 6" BASE = 1,375 LBS PER VERTICAL FOOT = 867 LBS 6" TOP SLAB = 1,575 LBS</p>	<p>PRECAST 48" DIAMETER MANHOLE ASSEMBLY-SANITARY WITH T-LOCK LINING</p>	<p>GARDEN STATE PRECAST FARMINGDALE, N.J. PHONE #: 732-938-4436 FAX #: 732-938-7096</p>
---	---	--	---